

15-145-009418 0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 12 1973

CONSERVATION DIVISION
Wichita, Kansas

11-12-1973

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name A. L. Abercrombie, Inc.

Complete Address 801 Union Center, Wichita, Kansas 67202

Lease Name Hutchinson "C" Well No. 4

Location C: SW/4 Sec. 9 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4380'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Bulling

Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 11:30 A Day 8 Month 11 Year 1973

The above well was plugged as follows:

Total Depth 4380' . 8 5/8 csg set at 245' cwc 200 sk.

5 1/2 csg set at 4379' cw 175 sk cem.

5 1/2 csg PBD 4271' & perf. (4236-4241)

Filled 5 1/2 csg W/sd (4220-4271) dumped 5 sk cmt W/dump bailer. (4185-4220)

Cutoff and recovered 3140' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, released plug and

pumped 100 sk comm cem. W/2% gel by Sun Cementing Co. Max. PP 400# SIP 250#.

I hereby certify that the above well was plugged as herein stated.

Signed: Boz Murray
Well Plugging Supervisor

INVOICED
DATE 11/12/73
INV. NO. 8153-10