

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

5-15-1969  
RECEIVED  
STATE CORPORATION COMMISSION  
MAY 15 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Colorado Oil Company 15-145-00194-6000

Complete Address: 915 Union National Bldg., Wichita, Kansas 67202

Lease Name Hutchinson "A" Well No. 1

Location NW NW SE Sec. 9 Twp. 23 Rge. 17 (E) (W) XX

County Pawnee Total Depth 4359

Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 2P Day 13 Month 5 Year 1969

The Above well was plugged as follows:

Total Depth 4359' 8 5/8 csg set at 222' cwc

5 1/2 csg set at 4358 8

5 1/2 csg PBT 4346 with top perf. (4220)

Filled 5 1/2 csg W/sd (4200-4346) Dumped 5 sk cmt W/dump bailer. (4160-4200)

Shotoff and recovered 3200' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 5/15/69  
INV. NO. 9770-4

Signed: Leo F. Massey  
Well Plugging Supervisor