

15-145-80828-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 22 1971  
CONSERVATION DIVISION  
Wichita, Kansas

11-22-1971

Operator's Full Name Kewanee Oil Company  
Complete Address Box 360 Hosington, Kansas 67514  
Lease Name Schartz "B" Well No. 4  
Location SW NW NE Sec. 7 Twp. 23 Rge. (E) (W) 17  
County Pawnee Total Depth 4360'  
Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated       
Plugging Contractor Southwest Casing Pulling  
Address Box 364 Great Bend, Kansas License No. 399  
Operation Completed: Hour 12 N Day 16 Month 11 Year 1971

The above well was plugged as follows:

Total Depth 4360' 8 5/8 csg set at 205' cwc 175 sk.

5 1/2 csg set at 4359' cw 175 sk cmt.

5 1/2 csg PBTB 4326' with top perf. (4208-4218)

Filled 5 1/2 csg W/sd (4175-4326) Dumped 5 sk cmt W/dump bailer. (4140-4175)

Cutoff and recovered 3235' of 5 1/2 csg.

Pumped down 8 5/8 csg with 10 sk gel & water W/300 lbs hulls, released plug and pumped 100 sk comm cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Wansley  
Well Plugging Supervisor

DATE 11-29-71

INV. NO. 4688-11