

KANSAS

JP

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-145-00827-0000

RECEIVED
STATE CORPORATION COMMISSION
NOV 22 1971
CONSERVATION DIVISION
Wichita, Kansas

11-22-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Kewanee Oil Company

Complete Address Box 360 Hosington, Kansas 67544

Lease Name Schartz "B" Well No. 3

Location NW NE NE Sec. 7 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4313'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 11 A Day 16 Month 11 Year 1971

The above well was plugged as follows:

Total Depth 4313' 8 5/8 csg set at 205' cwc 175 sk.

5 1/2 csg set at 4312' cw 150 sk cmt.

5 1/2 csg FBTD 4272' with top perf. (4207-4214)

Filled 5 1/2 csg w/sd (4175-4272) Dumped 5 sk cmt W/dump bailer. (4135-4175)

Cutoff and recovered 2230' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, release plug and

pumped 100 sk comm cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 11-29-71

INV. NO. 4684-W