

15-145-00825-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 22 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
11-22-1971

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Kewanee Oil Company

Complete Address Box 360 Hosington, Kansas 67514

Lease Name Schartz "B" Well No. 1

Location NE NE NE Sec. 7 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4313'

Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 9:15 A Day 16 Month 11 Year 1971

The above well was plugged as follows:

- Total Depth 4313' 8 5/8 csg set at 205' cwc 170 sk.
- 5 1/2 csg set at 4312' cw 150 sk cmt.
- 5 1/2 csg PBTB 4301' with perf. (4197-4202)
- Filled 5 1/2 csg W/sd (4175-4301) Dumped 5 sk cmt W/dump bailer. (4140-4175)
- Cutoff and recovered 3200' of 5 1/2 csg.
- Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, release plug and
- pumped 100 sk comm cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. F. Manning  
Well Plugging Supervisor

DATE 11-29-71

INV. NO. 4686-d