

KANSAS
STATE CORPORATION COMMISSION

15-145-00824-0000

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 10 1963

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas
6-10-1963

Operator's Full Name Phillips Pet Co

Complete Address: Box 287 Great Bend, Kans

Lease Name Godfrey Well No. A-8

Location NW NW SE Sec. 7 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4382

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Gasing Pulling

Address: Chase, Kansas License No. 436

Operation Completed: Hour 10AM Day 7 Month 6 Year 63

The Above well was plugged as follows:

9 5/8" 860' circulated with cement - 7" 4378' with 50 sax cement - PB to 4346' - Perf 4248'.

Filled with sand to 4200', set 5 sax cement with dump bailer - pulled 3100' 7" to 500', circulated hole with heavy mud through 7" at 500' (20 sax Gel), displaced 20 sax cement through 7" at 350', heavy mud to 160', displaced 20 sax cement through 7" at 160', heavy mud to 35', set bridge and filled to bottom cellar with cement.

Mudding and cementing by Knight Company Pump Truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edon Lee
Well Plugging Supervisor

DATE 6/11/63
INV. NO. 9233-11