

KANSAS



STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

15-145-00823-0000

2110

RECEIVED  
STATE CORPORATION COMMISSION

JAN 26 1973

CONSERVATION DIVISION  
Wichita, Kansas

1-26-1973

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Robin Supply Corporation

Complete Address 1322 E. 50th St. Tulsa, Oklahoma 74105

Lease Name Godfrey "A" Well No. 7

Location NW SW SE Sec. 7 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4382'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Southwest Casing Pulling Co.

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 3: P Day 24 Month 1 Year 1973

The above well was plugged as follows:

Total Depth 4382' 9 5/9 csg set at 866' cwc 545 sk.

7" csg set at 4378' cw 100 sk cmt.

7" csg PBD 4345' & perf. (4235-4299)

Filled 7" csg W/sd (4200-4345) Dumped 6 sk cmt W/dump bailer. (4165-4200)

Cutoff and recovered 2110' of 7" csg.

Pumped down 9 5/8" csg with 25 sk gel & water W/300 lbs hulls, -released 9 5/8 plug

and pumped 120 sk cmt. by Allied Cementing Co. PP 400 lbs. SI pres. 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed Leo A. Massey  
Well Plugging Supervisor

DATE 1/30/73

INV. NO. 6909-W