

Y
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-145-00822-0000

RECEIVED
STATE CORPORATION COMMISSION

OCT 12 1965

CONSERVATION DIVISION
Wichita, Kansas

10-12-1965

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Phillips Pet Co
Complete Address: Box 287 Great Bend, Kans
Lease Name Godfrey Well No. A-6
Location SW NE SE Sec. 7 Twp. 23 Rge. (E) (W) 17
County Pawnee Total Depth 4570
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Knight Casing Pulling Co
Address: Chase, Kans License No. 456
Operation Completed: Hour 11AM Day 9 Month 10 Year 65

The Above well was plugged as follows:

9 5/8" 859' circulated with cement - 7" 4366' with 90 sax cement
PB to 4535' - Perf 4216'
Set plug at 4200', sand to 4150', set 5 sax cement with dump bailer-
pulled 2090' 7" to 500' circulated hole with heavy gel mud through 7"
at 500' (25 sax Gel) - displaced 20 sax cement through 7" at 400', heavy
mud to 200', displaced 20 sax cement through 7" at 200', heavy mud to
55', set bridge and 10 sax cement to bottom cellar.
Mudding and cementing by Knight Company pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Eldon Petty*
Well Plugging Supervisor

DATE 10/12/65
INCH. 1943-W