

15-145-00821-0000

Form CP-3
Rev. 6-4-68

RECEIVED
STATE CORPORATION COMMISSION

JAN 26 1973

CONSERVATION DIVISION
Wichita, Kansas

1-26-1993

KANSAS

AL
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Robbin Supply Corporation

Complete Address 1322 E. 50th St. Tulsa, Oklahoma 74105

Lease Name Godfrey "A" Well No. 5

Location SE NW SE Sec. 7 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4371'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Co.

Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 10 A Day 24 Month 1 Year 1973

The above well was plugged as follows:

Total Depth 4371' 9 5/8 csg set at 843' cwc 450 sk.

7" csg set at 4367' cw 50 sk cmt.

7" csg PBTD 4345' with perf. (4227-4281)

Filled 7" csg W/sd (4200-4345) Dumped 6 sx cem. W/dump bailer. (4165-4200)

Cutoff and recovered 2465' of 7" csg.

Pumped down 9 5/8" csg with 25 sk gel & water W/300 lbs hulls, -released 9 5/8 plug

and pumped 120 sk cmt by Allied Cementing Co. PP 400 lbs. SI pres. 250 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Manning
Well Plugging Supervisor

INVOICED

DATE 1/30/73

INV. NO. 6908-11