

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-145 - 60820 - 0600

RECEIVED  
STATE CORPORATION COMMISSION

FEB 10 1965

CONSERVATION DIVISION  
Wichita, Kansas

2-10-1965

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Phillips Pet Co

Complete Address: Box 287 Great Bend, Kans

Lease Name Godfrey Well No. A-4

Location NE NE SE Sec. 7 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4369

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Knights Casing Pulling

Address: Chase, Kansas License No. 436

Operation Completed: Hour 6:30PM Day 8 Month 2 Year 65

The Above well was plugged as follows:

9 5/8" 861' circulated with cement. - 7" 4369' - PB to 4369' Perf 4228'

Filled with sand to 4210' - set 5 sax cement with dump bailer - pulled

2022' 7" to 800', circulated hole with heavy gel mud through 7" at 800'

( 25 sax Gel ) displaced 30 sax cement through 7" at 500', heavy mud to

170', displaced 30 sax cement through 7" at 170', heavy mud to 30', set

bridge and 10 sax cement to bot+om cellar.

Mudding and cementing by Knight Company pump truck.

I hereby certify that the above well was plugged as herein stated.

DATE 2/10/65  
INV. NO. 670-11

Signed: Redon Petty  
Well Plugging Supervisor