

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-145-00818-0000

RECEIVED  
STATE CORPORATION COMMISSION

JAN 26 1973

CONSERVATION DIVISION  
Wichita, Kansas

1-26-1973

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Robbin Supply Corporation

Complete Address 1322 S. 50th St. Tulsa, Oklahoma 74105

Lease Name Godfrey "A" Well No. 2

Location SW SW SE Sec. 7 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4405'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Southwest Casing Pulling Co.

Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 11:30 A Day 24 Month 1 Year 1973

The above well was plugged as follows:

Total Depth 4405' @ 5/8 csg set at 3857' cwc 450 sk.

7" csg set at 4401' cw 150 sk cmt.

7" csg PBD 4376' and perf. (4230-4322)

Filled 7" csg W/sd (4200-4376) Dumped 6 sk cmt W/dump bailer. (4165-4200)

Cutoff and recovered 2100' of 7" csg.

Pumped down 9 5/8 csg with 25 sk gel & water W/300 lbs hulls, -released 9 5/8 plug

and pumped 120 sk cmt by Allied Cementing Co. PP 350 lbs. SI pres. 200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey  
Well Plugging Supervisor

DATE 1/30/73

INV. NO. 6906-W