

R KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-145-00817-0000

RECEIVED
STATE CORPORATION COMMISSION
JUN 19 1972
CONSERVATION DIVISION
Wichita, Kansas

6-19-1972

Operator's Full Name Robbin Supply Corporation
Complete Address 1322 E. 50th St. Tulsa, Oklahoma 74105
Lease Name Godfrey "A" Well No. 1
Location SE SE SE Sec. 7 Twp. 23 Rge. (E) (W) 17
County Pawnee Total Depth 4313'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Flint Engineering & Const.
Address Box 342 Eldorado, Kansas 67042 License No. 547
Operation Completed: Hour 10 A Day 15 Month 6 Year 1972

The above well was plugged as follows:

Total Depth 4313' 9 5/8 csg set at 838' cwc 425 sk.

7" csg set at 4305' cw 150 sk cmt.

Filled 7" csg W/sd (4280-4313) Dumped 6 sk cmt W/dump bailer. (4255-4280)

Cutoff and recovered 2300' of 7" csg.

Mud to 375' -Set rock & sand bridge (350-375)

Dumped 5 yds readymix cmt from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Messerly
Well Plugging Supervisor

INVOICED

DATE 6/20/72

INV. NO. 5912-W