

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-145-00301-0006

RECEIVED
STATE CORPORATION COMMISSION

AUG 14 1972

CONSERVATION DIVISION
Wichita, Kansas

8-14-1972

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Bovaird Supply Company

Complete Address Box 48 Great Bend, Kansas 67530

Lease Name Godfrey Well No. 1

Location SE NE NW Sec. 7 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4329'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 10 A Day 11 Month 8 Year 1972

The above well was plugged as follows:

Total Depth 4329' 8 5/8 csg set at 210' cwc 200 sk.

5 1/2 csg set at 4327' cw 150 sk cmt.

5 1/2 csg perf. (3910-4002) & (4124-4288)

Filled 5 1/2 csg W/sd (3875-4329) dumped 5 sk cmt W/dump bailer. (3840-3875)

Cutoff and recovered 3320' of 5 1/2 csg.

Pumped down 8 5/8 csg with 25 sk gel & water W/500 lbs hulls, -released plug and

pumped 100 sk comm cmt W/2% CC.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Murray
Well Plugging Supervisor

DATE 8/15/72
INV. NO. 6161-4