

15-145-61339-0000

Form GP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1964

CONSERVATION DIVISION
Wichita, Kansas

12-21-1964

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Rock Island Oil & Refg Co
Complete Address: 321 W Douglas Wichita, Kansas
Lease Name Anderson Well No. 5
Location CS 1/2 NW NW Sec. 10 Twp. 23 Rge. (E) (W) 17
County Pawnee Total Depth 4270
Abandoned Oil Well x Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Southwest Casing Pulling
Address: Great Bend, Kans License No. 399
Operation Completed: Hour 5PM Day 14 Month 12 Year 64

The Above well was plugged as follows:

8 5/8" 238' circulated with cement - 5 1/2" 4258' with 125 sax cement
PB to 4240' - Perf 4202'

Filled with sand to 4180', set 4 sax cement with dump bailer, pulled
2490' 5 1/2" - pumped hole full heavy gel mud (³⁵ 55 sax Gel) pumped wiper plug
followed by 100 sax cement - cement to 0' - 200# pump pressure.

Mudding and cementing by Southwest Casing Pulling pump truck.

I hereby certify that the above well was plugged as herein stated.

DATE 12/21/64
INV. NO. 392-W

Signed: [Signature]
Well Plugging Supervisor