

15-145-01338-0000

Form CP-3
Rev. 6-26-62

10
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1964

CONSERVATION DIVISION
Wichita, Kansas

12-21-1964

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Rock Island Oil & Refg Co
Complete Address: 321 W Douglas Wichita, Kansas
Lease Name Anderson Well No. B-4
Location NE SW NW Sec. 10 Twp. 23 Rge. (E) (W) 17
County Pawnee Total Depth 4263
Abandoned Oil Well x Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Southwest Casing Pulling Co
Address: Great Bend, Kans License No. 399
Operation Completed: Hour 4PM Day 16 Month 12 Year 64

The Above well was plugged as follows:

8 5/8" 248' circulated with cement - 5 1/2" 4262' with 125 sax cement.
Perf at 4215'

Filled with sand to 4200', set 4 sax cement with dump bailer, pulled
2615' 5 1/2" - pumped hole full heavy mud (35 sax Gel), pumped wiper
plug followed by 100 sax cement - 250# pump pressure.

Mudding and cementing by Southwest Casing Pulling pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 12/21/64
INV. NO. 371-W

Signed: E. J. Perry
Well Plugging Supervisor