

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-145-01336-0000

RECEIVED
STATE CORPORATION COMMISSION
2 JAN 16 1967
1-16-1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Rock Island Oil & Ref. Co. Inc.,

Complete Address: 321 West Douglas Wichita, Kansas

Lease Name Anderson "B" Well No. 2

Location NW NW NW Sec. 10 Twp. 23 Rge. 17 (E) (W) X

County Pawnee Total Depth 4300'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Chase, Kansas License No. 436

Operation Completed: Hour 10 A Day 13 Month 1 Year 1967

The Above well was plugged as follows:

Total Depth 4300' 10 3/4 casing set at 266' cwc.

5 1/2 casing set at 4299' cw 150 sc cement.

PB 4248' Top Perf. 4202' --- Sand back to 4180' and dumped 5 sc cement with dump bailer.

Recov. 2600' of 5 1/2 csg.

Squeezed 10 3/4 csg with 40 sc gel mud and 150 sc cement. Shut in 150 lbs. pres.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. F. Massey
Well Plugging Supervisor

DATE 1/16/67

INV. NO. 4611-w