

15-145-01335-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 15 1969
CONSERVATION DIVISION
Wichita, Kansas

5-15-1969

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Colorado Oil Company

Complete Address: 915 Union National Bldg., Wichita, Kansas 67202

Lease Name Anderson Well No. 4

Location N/2 S/2 SW Sec. 10 Twp. 23 Rge. (E) (W) 17

County Ellis Total Depth 4360

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 12:30P Day 13 Month 5 Year 1969

The Above well was plugged as follows:

Total Depth 4360' 8 5/8 csg set at 236' cwc 175 sk.

5 1/2 csg set at 4359' cw 175 sk cmt.

5 1/2 csg PBSD 4264' and perf. (4236-4246)

Filled 5 1/2 csg W/sd(4220-4264) Dumped 5 sk cmt W/dump bailer. (4180-4220)

Shutoff and recovered 3212' of 5 1/2 csg.

Pumped thru 8 5/8 plug container With 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo A. Massey
Well Plugging Supervisor

INVOICED

DATE 5/15/69
INV. NO. 9769-w