

15-145-01374-0001

Form CP-3  
Rev. 6-26-62

KANSAS

10

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 15 1969  
CONSERVATION DIVISION  
Wichita, Kansas

5-15-1969

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Colorado Oil Company

Complete Address: 915 Union Nat'l Bldg., Wichita, Kansas

Lease Name Anderson Well No. 2

Location NW NW SW Sec. 10 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4340'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Knight Casing Pulling, Co.

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 10:30A Day 13 Month 5 Year 1969

The Above well was plugged as follows:

Total Depth 4340' 8 5/8 csg set at 246' cwc 175 sk.

5 1/2 csg set at 4339' cw 175 sk cmt.

5 1/2 csg FBTD 4307' Perf. (4237-4243)

Filled 5 1/2 csg W/sd (4225-4307) Dumped 5 sk cmt W/dump bailer. (4185-4225)

Cutoff and recovered 3206' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey  
Well Plugging Supervisor

INVOICED  
DATE 5/15/69  
INV. NO. 9767-W