

KANSAS

*Y*  
STATE CORPORATION COMMISSION

15-145-00298-0000

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 15 1969  
CONSERVATION DIVISION  
Wichita, Kansas

5-15-1969

Operator's Full Name Colorado Oil Company

Complete Address: 915 Union National Bldg., Wichita, Kansas

Lease Name Anderson Well No. 3

Location NE NE SW Sec. 10 Twp. 23 Rge. (E) (W)17

County Pawnee Total Depth 4310

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 4:45P Day 13 Month 5 Year 1969

The Above well was plugged as follows:

Total Depth 4310' 8 5/8 csg set at 277' cwc 175 sk.

5 1/2 csg set at 4309' cw 175 sk cmt.

5 1/2 csg PBFD 4220 with perf. (4206-10)

Filled 5 1/2 csg W/sd (4200-4220) Dumped 5 sk cmt W/dump bailer.

Shutoff and recovered 3200' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls plug and 100 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Red A. Massey  
Well Plugging Supervisor

INVOICED  
DATE 5/15/69  
INV. NO. 9768-4