

1030364

15-145-21120-0000 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Not Available
C N/2 N/2 SE, SEC. 8, T 23 S, R 17 W/8

2310 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050

Lease Name Garfield Well # 1

Operator: Kelso Casing Pulling / Mustang Drly
Name & Address: P. O. Box 347, Chase, KS 67524

County Pawnee License Number 143.00

Well Total Depth 4400 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 459

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:00 am Day: 15 Month: January Year: 1985

Plugging proposal received from Clay Duntz

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" set at 4399' Perfs at 4204-13, 4216-18, 4284-87, 4329-32

1st plug sand back to 4150' and dump 5 sx cement on top of sand through bailer
2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 125 sx cement

Plugging Proposal Received by Robert Tarbutton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 pm Day: 16 Month: January Year: 1985

ACTUAL PLUGGING REPORT 1st plug sanded back to 4150' and dump 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
1-30-1985
JAN 30 1985

Maximum pressure 400 psi and shut in 200 psi

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.
(additional description is necessary, use BACK of this form.)

INVOICED

(did / ~~XXXXXX~~) observe this plugging.

DATE 2-6-85

Signed Steve Duntz (TECHNICIAN)

INV. NO. 6850