

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15-145-10000-0600
API NUMBER 15-~~047~~ ~~7611~~ SK

CNE, SEC. 9, T23 S, R170E

FEET FROM N/S SECTION LINE

FEET FROM W/E SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5423 ⁵³⁹³

LEASE NAME Hutchinson WELL # D # 12

OPERATOR: A.L. Abercrombie Inc.
NAME & ADDRESS: 801 Union ctr.
Wichita, Kan. 67202

COUNTY Pawnee

WELL TOTAL DEPTH 4331 \$140.76 FEET

CONDUCTOR PIPE: SIZE FEET

SURFACE CASING: SIZE 8 5/8 FEET 245

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL D&A _____

OTHER WELL AS HEREINAFTER INDICATED Hutchinson D #12 SWD

PLUGGING CONTRACTOR Abercrombie LICENSE NUMBER 5423

ADDRESS SAME

COMPANY TO PLUG AT: HOUR: 10 AM DAY: 23 MONTH: 6 YEAR: 1983

PLUGGING PROPOSAL RECEIVED FROM Ed Abercrombie

(COMPANY NAME) SAME (PHONE) 262-1841

WERE: 4 1/2" @ 4330 w/1504 P3TD 3710 PACKER STUCK

Plug: Run tubing to 3700 and pump 5 sx frac sand + 25 sx cement - Pull tubing to 1200' and circ gel mud to surface. Pump 25 sx at 1000' pull up to 400' and circ cement to 0' w/40 sx. Holes in surface pipe 40' below

PLUGGING PROPOSAL RECEIVED BY Steve Bennett (TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 9:00 DAY: 27 MONTH: 6 YEAR: 1983

ACTUAL PLUGGING REPORT

Surface. Run 1" tubing to 425' pump 140 sx cement would not circ. Wire line cement top @ 131' - Fill rest of pipe with cement.

REMARKS: 60/40 Pacing 2% gel - 3% cc by Stan Conroy

RECEIVED STATE CORPORATION COMMISSION

JUL 07 1983

7-7-1983 CONSERVATION DIVISION Wichita, Kansas

I (DID / DID NOT) OBSERVE THIS PLUGGING.

INVOICED

DATE 7-12-83

INV. NO. 4801 W

SIGNED Steve Bennett (TECHNICIAN) ✓

FORM CP-2/3 REV. 6-83