

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-00848-00-00  
Spot: S2NENESE Sec/Twnshp/Rge: 9-23S-17W  
2175 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: HUTCHINSON D Well Number: 7  
County: PAWNEE Total Vertical Depth: 4290 feet

Operator License No.: 32302  
Op Name: KEY GAS CORP.  
Address: 155 N. MARKET - SUITE 900  
WICHITA, KS 67202

Conductor Pipe: Size 10.75 feet: 239 8139.43  
Surface Casing: Size feet:  
Production: Size 7 feet: 4209 WITH 125 SX CMT  
Liner: Size 5.5 feet: 4291 WITH 125 SX CMT

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/17/2002 9:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND BACK TO 4140' & 7 SX CMT. PLUG AT 1246' WITH 20 SX GEL & 80 SX CMT. PLUG AT 450' WITH 50 SX CMT. PLUG AT 260' WITH 80 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: RICHARD LACEY  
Date/Time Plugging Completed: 12/17/2002 3:00 PM

WitnessType: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: RICHARD LACEY

Actual Plugging Report:


PBTD 4290'. PERFS AT 4208-4265'. SANDED TO 4140' & 7 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING. PLUG AT 1240' WITH 20 SX GEL - 80 SX CMT WITH 200# HULLS. 2ND PLUG AT 450' WITH 50 SX CMT. 3RD PLUG AT 260' WITH 80 SX CMT. 4TH PLUG AT 40' WITH 30 SX CMT.

RECEIVED  
DEC 30 2002 12-30-2002  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2030' OF 7" CASING.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

INVOICE

DATE 12-31-02

WVZ NO. 2003061004