

1 030198

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,136-0600

SW NW NE, SEC. 15, T 23 S, R 17 (W/E)

990 feet from N/E section line

2310 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6343

Lease Name Giles Well # 1

Operator: Yost Oil Operations, Inc.

County Pawnee

Name & Address Box 811

Well Total Depth 4350 141.38 feet

Russell, KS 67665

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 708

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Emphasis Oil Operations License Number 8241

Address 120 West Third, Russell, KS 67665

Company to plug at: Hour: 2:00 pm Day: 14 Month: June Year: 19 84

Plugging proposal received from Bill Owen

(company name) Emphasis (phone) 913-483-3518

were: to fill hole with heavy mud and spot cement through drill pipe 6-18-1984

1st plug at 1100' with 100 50 sx cement

2nd plug at 750' with 40 sx cement

solid bridge  
3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement.

5th plug to circulate rat hole with 15 sx cement

RECEIVED  
STATE CORPORATION COMMISSION

JUN 18 1984

CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Steve Plummer (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 4:45 pm Day: 14 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1100' with 100 50 sx cement, 2nd plug at 750' with 40 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied. hole fluid was below plugging depth. (if additional description is necessary, use BACK of this form.)  
we had to re-do 1st plug because

INVOICED

(customer) observe this plugging.

DATE 6-25-84

Signed Steve Plummer (TECHNICIAN)

INV. NO. 2131

6-14