

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-145-06141-0000  
NE 1/4, Sec. 15, T 23 S, R 17 W  
NUNUNNE feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5673  
Operator: W. L. KIRKMAN, INC  
Name & Address P.O. Box 195  
Pratt, KS 67124

feet from W/E section line  
Lease Name Slegake Well # 1  
County Pawnee  
Well Total Depth 4459 feet #144.92  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 345'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address Box 176, Chase, KS 67524

Company to plug at: Hour: 10:30 AM Day: 6 Month: April Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Bill Fulls  
(company name) Kelso (phone)

were: to sand bottom to 4125 w/5 sf cmt on top,  
then recover pipe and use 50/50 permix,  
2% gel - 3% cc for the following sequence:  
2 sf hulls, 15 sf gel, 70 sf cmt, 5 sf gel, 8 5/8  
wiper plug released, then finish w/100 cmt.

Signed R. Barbutan (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:15 pm Day: 6 Month: April Year: 1983

ACTUAL PLUGGING REPORT Plugged as ordered. Maximum  
pump pressure 800#; shut in pressure  
@ 400#, cementing by Sun.

Mr. Steve Duriant observed this plugging.

Remarks: 8 5/8 cemented w/175 sf; 5 1/2 set @ 4340 w/100 sf  
recovered 680' - Perfs 4184-4192 - RECEIVED  
STATE CORPORATION COMMISSION

APR 12 1983  
4-12-1983  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given and that I (did / did not) observe this plugging.

INVOICED

DATE 4-20-83  
INV. NO. 4067-W

Signed R. Barbutan (TECHNICIAN)