

1 121010

1-18

B-145-00860-00-01

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #E-13,723
200' S of
C N/2 NW, SEC. 15, T 23 S, R 17 W/E
4400 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5446

Lease Name Fertig Well # 3

Operator: Benjamin M. Giles
Name & Address
532 S. Market
Wichita, KS 67202

County Pawnee
Well Total Depth 4360 141.70 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 249

Abandoned Oil Well _____ Gas Well _____ Input Well SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Greensburg Well Service License Number _____

Address P.O. Box 632, Greensburg, KS 67054-0632

Company to plug at: Hour: 9 a.m. Day: 18 Month: 1 Year: 19 95

Plugging proposal received from Ben Giles

(company name) Benjamin M. Giles (phone) 316-265-1992

were: 5 1/2" at 4357' w/175 sx cement, PBDT 3650', Perfs at 4222-78', Squeezed at 1500' w/300 sx cement

1st plug run tubing to 4220' and pump 10 sx gel and 20 sx cement,

2nd plug pull tubing to 1160' and circulate 5 1/2",

3rd plug pump 100 sx cement down 8 5/8" X 5 1/2" annulus.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 18 Month: 1 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug ran tubing to 3400' and pumped 10 sx gel followed by 50 sx cement with 100 lbs. hulls mixed in cement,

2nd plug pulled tubing to 1000' and circulated cement with 90 sx,

3rd plug pulled all tubing and topped off with 15 sx cement,

4th plug pumped in 8 5/8" X 5 1/2" annulus with 70 sx cement.

Pumping pressure 0-400 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 2-3-95

Signed Duane Rankin (TECHNICIAN)

INV. NO. 42141

MAR 16 1995 APR 26 1995