

1 120867

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200, COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-20,903-00-01

SW SW NE, SEC. 11, T 23 S, R 17 W/4E
2970 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Giles Well # 1

Operator: Oil Producers, Inc. of Kansas

County Pawnee

Name & Address P.O. Box 8647

Well Total Depth 2275 73.94 feet

Wichita, KS 67208

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 275

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Oil Producers, Inc. of Kansas License Number 8061

Address P.O. Box 8647, Wichita, KS 67208

Company to plug at: Hour: 1 p.m. Day: 15 Month: 12 Year: 1993

Plugging proposal received from Brad Siroky

(company name) Oil Producers, Inc. of Kansas (phone) 316-681-0231

vers: 4 1/2" casing set at 2274' cemented w/175 sx, Perfs at 2179-82', 2188-92'

1st plug pump 150 sx cement down backside.

2nd plug fill casing volume.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:30 p.m. Day: 15 Month: 12 Year: 1993

ACTUAL PLUGGING REPORT 1st plug pumped in 8 5/8" X 4 1/2" annulus with 150 sx cement

(60/40 Pozmix 6% gel). No pressure, no vacuum.

2nd plug pumped in 4 1/2" casing with 120 sx cement (60/40 Pozmix 3% gel). Pumping pressure

0-300 psi and shut in 100 psi.

12-21-1993
RECEIVED
STATE CORPORATION COMMISSION
WICHITA, KANSAS
DEC 27 1993

Remarks: Cemented by Allied. No casing recovery. Recently washed down-never produced.
(If additional description is necessary, use BACK of this form.)

(All 8/1/93) observe this plugging.

Signed Dawn Rankin (TECHNICIAN)

DATE 12-30-93

INV. NO. 39600 FEB 23 1994
12-15