

To: 1 120859  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

11-15 AP) NUMBER 15-145-21,209-0000

N/2 N/2 NW, SEC. 16, T 23 S, R 17 W/EX

4950 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086  
Operator: Pintail Petroleum Ltd.  
Name & Address: 225 N. Market, Ste. 300  
Wichita, KS 67202

Lease Name Martha Well # 2  
County Pawnee 143.65  
Well Total Depth 4420 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 337

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 15 Month: 11 Year: 19 93

Plugging proposal received from Mike Kelso  
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4419' w/125 sx cement, PBSD 4375', Perfs at 4348-52'  
1st plug sand back to 4300' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 150 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 19 1993 11-19-1993

Plugging Proposal Received by Richard Lacey (TECHNICIAN)  
Wichita, Kansas

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 1 p.m. Day: 15 Month: 11 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4300' and dumped 4 sx cement on  
top of sand through bailer,  
2nd plug pumped into 8 5/8" surface casing with 250 lbs. hulls, 10 sx gel, 50 sx cement, 10  
sx gel, 150 lbs. hulls and 150 sx cement.  
Pumping pressure 0-500 psi and shut in 50 psi.  
Welded 8 5/8" plate & 5 1/2" collar on 8 5/8" surface casing.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2310' of 4 1/2" casing.

INVOICED

DATE NOV 23 1993  
I (did / reserve this plugging.

INV. NO. 39284

Signed Dean Rankin (TECHNICIAN)