

**Kansas Corporation Commission**

**District Plugging Report**

API Well Number: 15-003-02601-00-00  
 Spot: SENE Sec 1 Twp 21 S Rng 19 ☒ E / ☐ W  
4355 Feet from ☐ N / ☒ S Line of Section  
350 Feet from ☒ E / ☐ W Line of Section  
 GPS: Lat: 38.253460 Long: 95.260100 Date: 3/16/17  
 Lease Name: Helen Merrill Well #: MER 01  
 County: Anderson Total Vertical Depth: 350 feet

Operator License No: 101 String Size Depth Pulled Comments  
 Op Name: State of Kansas DRIVE - Drive Pipe 8 10 0 EST  
 Address 1: 226 N Main St., Ste. 220 T1 - Tubing 1 2.000 750 2 EST  
 Address 2: \_\_\_\_\_  
 City: WICHITA  
 State: KS Zip Code: 67202 - \_\_\_\_\_

Well Type: OG - Oil & Gas (Oil) UIC Docket No.: \_\_\_\_\_ Date/Time to Plug: 2/26/18 / \_\_\_\_\_  
 Plug Co License No.: 3097 Plug Co. Name: K-W OIL WELL SERVICES, INC.  
 Proposal Revd from: Jim Kepley Company Name: K-W Phone: 620-431-2285

Fill well with portland cement from TD to surface.

Proposed  
 Plugging  
 Report:

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%  
 Date/Time Plugging Completed: 2/26/18 / \_\_\_\_\_ KCC Agent: FRANK GUILFOYLE

Actual Plugging Report: Perfs: Top Bottom Thru  
150 300 TBG - Tubing  
 Move equipment to location. Dig around well and level area. Set up rig, dig and fill pit. Drill out cement lined 2" pipe and cement inside 2" pipe. Drill to 350 ft. Perforate pipe. Run 1" inside 2" to 350 ft. Pump Portland cement to surface. Pull pipe and top off well. Pump total of 21 sacks of cement. Well plugged.

Remarks: Control No. 20170024-001. Contract No. 43069. GPS'ed by F. G. NAD 83. Irregular section.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: ☐ Yes ☐ No

District: 03

**KCC WICHITA**

**APR 05 2018**

**RECEIVED**

**4-5-2018**

*Frank Guilfoyle*  
 (Technician)

Form: District Plugging Report - \_\_\_\_\_