

District Plugging Report

Operator License No.: 101	String	Size	Depth	Pulled	Comments
Op Name: State of Kansas	DRIVE - Drive Pipe	8.000	10	0	EST.
Address 1: 266 N. Main St., Ste. 220					
Address 2:					
City: WICHITA					
State: KS Zip Code: 67202					
Well Type: OGE Oil & Gas (oil)	UIC Docket No.:	Date/Time to Plug: 8/28/17			
Plug Co License No.: 3097	Plug Co. Name: K-W OIL WELL SERVICES, INC.				
Proposal/Rcv'd from: JTM Kepley	Company Name: K-W	Phone: (620) 431-2285			

Proposed Plugging Report:	Fill well with portland cement from TD to surface. Well No. 1018 to Plug Co. Name: JACKSON WELL SERVICE, INC. Well Name: JACKSON WELL SERVICE, INC. Company Name: JACKSON WELL SERVICE, INC. Fill well with portland cement from TD to surface.
---	---

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%
Date/Time Plugging Completed: 8/28/17 KCC Agent: FRANK GUILFOYLE

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
-------------------------	--------	-----	--------	------

Move equipment to location. Dig around well and level area. Set up rig, dig and fill pit. Drill through cement cap. Drill through rocks, wood, and soil. Drill to 260 ft. Pull out drill steel and run 1" to 260 ft. Try to wash deeper and washed to 600 ft. Pump Portland cement from 600 ft to surface. Pull pipe and top off well. Pump total of 225 sacks of cement. Well plugged.

Remarks	Control No. 20170024-005. Contract No. 43069. GPS'ed by F. G. NAD 83. Irregular section.
---------	--

Plugged Thru: TBG - Tubing **RECEIVED** **Plugged Due to Compliance Issue:** ☐ Yes ☐ No

District: 03 on Dec 18 2017 Frank G. Smith

CONSERVATION DIVISION
 WICHITA, KS
 12-18-2017

(Technician)
 Form: District Plugging Report - _____
 Plugged by _____