

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-23500-00-00
Spot: W2NESE Sec/Twnshp/Rge: 30-15S-13W
1980 feet from S Section Line, 990 feet from E Section Line
Lease Name: TRAPP B Well #: BARTON 2
County: RUSSELL Total Vertical Depth: 3358 feet

Operator License No.: 31431
Op Name: BARTON EXPLORATION, INC.
Address: 3017 E 14TH ST
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3350		125 SX
SURF	8.625	802		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/31/2018 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: LONNIE BARTON Company: BARTON EXPLORATION, INC. DB Phone: (785) 650-0541

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Well was producing at 2000'. Plugged back to 2100'.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/31/2018 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1500' and 500'. Ran tubing to 1900' and pumped 100 sx cement w/450 # hulls.
Pulled tubing to 900' and pumped 75 sx cement. Pulled tubing to 600'. Circulated cement to surface with 50 sx cement on casing. Pulled tubing. Tied to casing and circulated cement to surface on backside with 65 sx cement.

GPS: 38.71622 -098.80392

Perfs:

INVOICED
JUL 12 2018

Remarks: QUALITY OILWELL CEMENTING

Plugged through: TBG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

JUN 05 2018

JUN 25 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

6-25-2018