

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-23001-00-00  
Spot: SWNENWNE Sec/Twnshp/Rge: 36-7S-21W  
650 feet from N Section Line, 1680 feet from E Section Line  
Lease Name: BENOIT Well #: 1-36  
County: GRAHAM Total Vertical Depth: 3589 feet

Operator License No.: 32819  
Op Name: BAIRD OIL COMPANY LLC  
Address: 113 W MAIN PO BOX 428  
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3588		425 SX
SURF	8.625	207		100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/14/2018 1:00 PM  
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING  
Proposal Revd. from: BRYANT REESE Company: BAIRD OIL COMPANY LLC DBA Phone: (785) 689-7456

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 13 sx gel and 500 # hulls.  
Port collar at 1664' w/185 sx cement.  
Production perforations: 3340' - 3345'.

Plugging Proposal Received By: PAT BEDORE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/14/2018 2:15 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2" casing and pumped 50 sx cement w/300 # hulls. Then pumped 13 sx gel followed by 175 sx cement. Shut in pressure 500#. Visually checked 8 5/8" x 5 1/2" annulus and cement was to surface.

GPS: 39.40693N -099.60826W

Perfs:

Top	Bot	Thru	Comments
3340	3345		

INVOICED  
JUL 12 2018

Remarks: GLOBAL CEMENTING TICKET # 3368

Plugged through: CSG

District: 04

Signed

Pat Bedore

Received  
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

JUN 18 2018

JUN 25 2018 6-25-2018

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3