

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-22218-00-00
Spot: NENWNW Sec/Twnshp/Rge: 24-7S-20W
330 feet from N Section Line, 990 feet from W Section Line
Lease Name: PERKINS Well #: 1
County: ROOKS Total Vertical Depth: 3555 feet

Operator License No.: 32819
Op Name: BAIRD OIL COMPANY LLC
Address: 113 W MAIN PO BOX 428
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3553		150 SX
SURF	8.625	258		155 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/13/2018 8:30 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: BRYANT REESE Company: BAIRD OIL COMPANY LLC DBA Phone: (785) 689-7456

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix 4% gel cement, 8 sx gel (100 # bags) and 500 # hulls.
Squeezed with 400 sx cement.
Production perforations: 3494' - 3500'.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/13/2018 9:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 4 1/2" casing and pumped 50 sx cement w/300 # hulls. Then pumped 8 sx gel followed by 145 sx cement. Shut in pressure 400#. Hooked to 8 5/8" x 4 1/2" annulus and pumped 5 sx cement w/750 # hulls.

GPS: 39.43654N -099.50647W

Perfs:

Top	Bot	Thru	Comments
3494	3500		

INVOICED
JUL 11 2018

INVOICED
JUL 1 2018
INVOICED

JUL 12 2018

Remarks: GLOBAL CEMENTING TICKET # 3366

Plugged through: CSG

District: 04

Signed _____

Pat Bedore

Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

JUN 18 2018

JUN 25 2018
6-25-2018
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3