

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-01256-00-00

Spot: NWNESESW

Sec/Twnshp/Rge: 2-26S-8E

1200 feet from S Section Line, 3140 feet from E Section Line

Lease Name: STEVENSON

Well #: W-5

County: GREENWOOD

Total Vertical Depth: 2345 feet

Operator License No.: 5394

Op Name: ABDERHALDEN, R. R.

Address: 100 S. MAIN, STE 510

WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2334		50 SX
SURF	8.63	83		15 SX

Well Type: EOR

UIC Docket No:

Date/Time to Plug: 06/04/2018 10:00 AM

Plug Co. License No.: 5656

Plug Co. Name: R.R.A., INC.

Proposal Rcvd. from: DARYL WHITEMAN

Company:

Phone: (316) 640-9072

Proposed
Plugging
Method:

Set a 50 ft cement plug at TD. Mud to 1000 ft. Shoot off pipe at 1000 ft. Pull pipe. Set a 50 ft cement plug at 1000 ft. Pull tubing to 150 ft. and cement to surface.

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: PARTIAL

Date/Time Plugging Completed: 06/04/2018 2:00 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

Ran tubing to 1500', iron in hole below 1500' not able to remove, pumped 20 sxs cement, @ 1500', pulled pipe to 1010', pumped 15 sxs cement, pulled tubing to 150' pumped 80 sxs cement, gel spacers between cement plugs, casing shot @ 1010' & 150'.

RECEIVED
KCC DIST # 3
JUN 11 2018
CHANUTE, KS

mt

Remarks:

Plugged through: TBG

INVOICED
JUL 12 2018

District: 03

Signed

Mike Deffen
(TECHNICIAN)

810 E 7TH
PO Box 92
EUREKA, KS 67045
(620) 583-5561



15073-01256 00 00

Cement or Acid Field Report
Ticket No. **3943**
Foreman Russell McCoy
Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
6-4-10	1046	STEVEN'S W5				G.W.	KS
Customer R.R.A. INC.			Safety Meeting	Unit #	Driver	Unit #	Driver
Mailing Address 100 S. MAIN ST. STE 510				102	Russ		
City Wichita				115	AB		
State KS				141	JASIN		
Zip Code 67202							

Job Type P.T.A. - old Hole Depth _____ Slurry Vol. _____ Tubing 2 3/8
Casing Depth _____ Hole Size _____ Slurry Wt. _____ Drill Pipe _____
Casing Size & Wt. 5 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other _____
Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety meeting, Pig to 2 3/8 Tubing
20 SKs 1500'
15 SKs 1010'
80 BSKs 150 to SURFACE (INSIDE + OUT)
115 SKs TOTAL

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-105	1	Pump Charge	750.00	750.00
C-107	20	Mileage	3.95	79.00
C-203	115	SKs 60/40 Peamin	12.75	1466.25
C-206	400 th	Gal = 4%	.20	80.00
C-108	4.95	Tow mileage	m/c	345.00
C-113	3 hr	80 Bbl VAC Truck	85.00	255.00
C-224	3,000	Gallons City water	10 th /1000	30.00
				3,005.25
			- 5%	< 1161.54 >
		Sales Tax		885.39
Authorization by <u>Darrel</u> Title <u>Co/Rep</u>			Total	3069.10

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.