

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-22607-00-00
Spot: SENWNWNW Sec/Twnshp/Rgc: 14-16S-30W
486 feet from N Section Line, 607 feet from W Section Line
Lease Name: WATT Well #: 1-14
County: LANE Total Vertical Depth: 4460 feet

Operator License No.: 32457 String Size Depth (ft) Pulled (ft) Comments
Op Name: ABERCROMBIE ENERGY, LLC SURF 8.625 302 WITH 210 SX CMT
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

Well Type: DH UIC Docket No: Date/Time to Plug: 05/20/2018 6:00 PM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: SID DEUTSCHER Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 2130' WITH 50 SX CMT. 2ND PLUG AT 1380' WITH 80 SX CMT. 3RD PLUG AT 700' WITH 50 SX CMT. 4TH PLUG AT 330' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: NONE
Date/Time Plugging Completed: 05/20/2018 8:00 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

Perfs:

1ST PLUG AT 2130' WITH 50 SX CMT. 2ND PLUG AT 1380' WITH 80 SX CMT. 3RD PLUG AT 700' WITH 50 SX CMT. 4TH PLUG AT 330' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY QES.

Plugged through: DP

District: 01

Signed


(TECHNICIAN)

RECEIVED
MAY 25 2018
KCC DODGE CITY

INVOICED

JUL 12 2018