

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-093-20467-00-00  
Spot: SE Sec/Twnshp/Rge: 10-22S-37W  
1273 feet from S Section Line, 1317 feet from E Section Line  
Lease Name: LUCILLE Well #: 1  
County: KEARNY Total Vertical Depth: 3100 feet

Operator License No.: 30481  
Op Name: APOLLO ENERGIES, INC.  
Address: 10378 N 281 HWY  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3060		
PROD	5.5	3100	0	WITH 550 SX CMT
SURF	8.625	399		WITH 339 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/17/2018 9:00 AM  
Plug Co. License No.: 34612 Plug Co. Name: EXACT WELL SERVICE LLC  
Proposal Rcvd. from: GARY PIESTER Company: EXACT WELL SERVICE LLC Phone: (620) 626-9779

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/17/2018 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 85 SX CMT WITH 100# HULLS & 30 7/8" BALL SEALERS DOWN 5 1/2" CASING. DISPLACE WITH WATER TO 2000' & PRESSURE TO 400#. HOLDING. RUN CBL FROM 1680' TO 30'. FOUND TOC BEHIND THE 5 1/2" CASING AT 448'. PERFORATE 3 HOLES AT 360'. INJECTION RATE 2 BPM AT 50 PSI. RUN TBG TO 1085' & CIRCULATE CMT TO SURFACE UP THE 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS USING 170 SX CMT. TOOH WITH TBG & TOP OFF WITH 15 SX CMT LEAVING CASING & ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2970	2980		
2952	2958		
2916	2926		

INVOICED  
JUL 12 2018

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

District: 01

Signed

  
(TECHNICIAN)  
58

RECEIVED  
MAY 24 2018  
KCC DODGE CITY