

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-02649-00-00  
Spot: S2N2 Sec/Twnshp/Rge: 3-33S-11W  
3258 feet from S Section Line, 2676 feet from E Section Line  
Lease Name: WILLIAMS Well #: 1  
County: BARBER Total Vertical Depth: 4570 feet

Operator License No.: 30481  
Op Name: APOLLO ENERGIES, INC.  
Address: 10378 N 281 HWY  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4400		WITH 2 SX CMT
PROD	4.5	4590	2517	WITH 125 SX CMT
SURF	8.625	278		WITH 250 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/09/2018 9:00 AM  
Plug Co. License No.: 30481 Plug Co. Name: APOLLO ENERGIES, INC.  
Proposal Revd. from: JIM BYERS Company: APOLLO ENERGIES, INC. Phone: (620) 672-9001

Proposed Plugging Method: PUMP 25 SX CMT WITH 150# HULLS ON BOTTOM. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: PARTIAL  
Date/Time Plugging Completed: 05/10/2018 12:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

CIBP @ 4400' WITH 2 SX CMT ON TOP WITH BAILER. 1ST PLUG AT 604' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 305' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4465	4490		

INVOICED  
JUL 12 2018

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed Stephen J. Pfajfer  
(TECHNICIAN)

RECEIVED  
MAY 22 2018  
KCC DODGE CITY