

6 062385

3-29

API NUMBER 15-009.15584.0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW, SEC. 24, T. 20S, R. 12 W/Ex
1650 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4656

Lease Name Buckbee Well # A-2

Operator: Davis Petroleum Inc.
Name & Address R. R. 1, Box 183 B
Great Bend, Ks. 67530

County Barton 108.68

Well Total Depth 3344 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 252

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 8:00AM Day: 29 Month: Mar Year: 19 91

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone) 316-938-2943

were: Order 450 sks 60/40 poz 8% gel 5 sks hulls.

RECEIVED
STATE CORPORATION COMMISSION
4-4-1991
APR 04 1991
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:45PM Day: 29 Month: Mar Year: 19 91

ACTUAL PLUGGING REPORT 8 5/8 set at 252 w/200 sks. 5 1/2 set at 3331 w/150 sks.

Top perf at 3023. Plugged bottom w/sand and 5 sks cement to 2975.

Pipe parted and recovered 310. Ran tubing to 650 and circ cement to surf.

Hooked onto 8 5/8 and sq to 300 psi w/330 sks cement. Could not fish casing.

Remarks: By Halliburton

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

DATE 4-11-91

Signed Gilbert G. Scheck (TECHNICIAN) E.A.S.

INV. NO. 31469