


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15.009.15593.0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Barton County, Sec. 24 Twp. 20 Rge. 12 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
440' S 1320' E of NW $\frac{1}{4}$   
Lease Owner Icer Addis  
Lease Name Pete Scheufler Well No. 3  
Office Address 5307 E. Central, Wichita, Kansas 67208  
Character of Well (Completed as Oil, Gas or Dry Hole)  
SWD



Locate well correctly on above  
Section Plat

Date Well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced Aug. 20 19 79  
Plugging completed Aug. 31 19 79  
Reason for abandonment of well or producing formation  
no longer needed  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3339'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
			245'	10 3/4"	245'	none
			3314'	7"	3314'	499.75

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded back to 3270' and dumped 6 sacks of cement.

Allied Cementing, Inc. plugged well pumping in 4 sacks of hulls, 10 sacks of gel and 175 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION

SEP - 7 1979 9-7-1979

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor GLENNS CASING PULLING INC. Conservation Division  
Box 413, Ellinwood, Kansas 67528

STATE OF KANSAS COUNTY OF BARTON, ss.  
Evelyn Roth (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth  
Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 5th day of September, 1979



Jenny Kasselmann  
Notary Public.

My commission expires

P. SCHEUFLER NO. 3

Spudded: January 20, 1941  
 Drlg. Completed: February 10, 1941  
 Potential Taken: February 12, 1941

Location: 440' S & 1320' E of the  
 NW Corner of Sec. 24, Twp. 20S,  
 Rge. 12W, Barton County, Kansas

From	To	Formation	From	To	Formation
0	257	Surface sand	2940	2986	Lime & shale
257	615	Shale & red bed	2986	3017	Lime
615	860	Sand & red bed	3017	3045	Lime & shale
860	1260	Shale & red bed	3045	3070	Shale
1260	1402	Shale	3070	3120	Lime & shale
1402	1536	Shale lime	3120	3144	Lime
1536	1653	Lime & shale	3144	3215	Lime shale
1653	1767	Shale lime	3215	3230	Shale
1767	1970	Lime & shale	3230	3270	Lime & shale
1970	2031	Lime	3270	3278	Lime hard
2031	2115	Shale & lime	3278	3310	Lime & shale
2115	2194	Lime	3310	3316	Shale lime
2194	2611	Lime shale	3316	3319	Dolomite
2611	2653	Lime	3319	3332	Hard lime
2653	2836	Lime shale	3332	3340	Lime
2836	2940	Lime		3339'	Total Depth from cement floor level.

Elevation from derrick floor level 1799'.

Run 246'1" of 10-3/4" OD 40# 8-thd lapweld surface casing; set at 245'; cemented with 225 sacks of cement.

Top of Arbuckle Lime 3313'.

Run 3232'8" of 7" OD 20# 8-thd "H-40" Smls. casing; set at 3314'; cemented with 250 sacks of cement.

Total fillup with oil 3100' - Swabbed 157 bbls. of oil in 1 hour - could not swab below 1000' from top of hole.

2/12/41 - Established an Echometer potential of 3000 bbls. of oil, no water.

Total Depth 3339'.

Note: All of above footages except elevation calculated from cement floor level.

FAD-JL  
 LPC (3)  
 File (1)

RECEIVED  
 STATE CORPORATION COMMISSION

MAY 22 1979

CONSERVATION DIVISION  
 Wichita, Kansas

I, the undersigned, being first duly sworn upon oath, state that this well record is true, correct and complete according to the records of this office and to the best of my knowledge and belief.

*F. L. D...*  
 Name and title of representative of company

Subscribed and sworn to before me this the 23rd day of April, 1941.

My Commission expires October 21, 1944 *Louis M. Lewis*  
 Notary Public

.....