

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Barton County. Sec. 24 Twp. 20 Rge. 12 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
440' S 440' W of N/4

Lease Owner Icer Addis  
Lease Name Pete Scheufler Well No. 5  
Office Address 5307 E. Central, Wichita, Kansas 67208  
Character of Well (Completed as Oil, Gas or Dry Hole) SWD.

Date Well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced Aug. 31 1979  
Plugging completed Aug. 31 1979

Reason for abandonment of well or producing formation  
no longer needed  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin  
Producing formation Depth to top Bottom Total Depth of Well 3819'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
			248'	9 5/8"	248'	none
			3554'	6"	3554'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Allied Cementing, Inc. plugged well pumping in 4 sacks of hulls, 35 sacks of gel and 200 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 7 1979

CONSERVATION DIVISION  
Wichita, Kansas 9-7-1979


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GLENN'S CASING PULLING INC.  
Box 113, Ellinwood, Kansas 67526

STATE OF KANSAS COUNTY OF BARTON, ss.  
Evelyn Roth (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth  
Ellinwood, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of September, 1979



My commission expires

Jenny Kasselmann  
Notary Public.

P. SCHEUFLER NO. 5

Spudded: February 17, 1941  
 Drlg. Completed: March 10, 1941  
 Potential Taken: Dry Hole

Loc: 440' S & 440' W of N/4 Corner  
 of Sec. 24, Twp. 20S, Rge. 12 W,  
 Barton County, Kansas

From	To	Formation	From	To	Formation
0	263	Surface Sand	3090	3125	Lime
263	718	Sand & red bed	3125	3150	Lime & shale
718	1353	Shale & red bed	3150	3240	Lime
1353	2033	Lime & shale	3240	3245	Soft lime
2033	2101	Lime	3245	3299	Lime
2101	2172	Shale & lime	3299	3343	Lime & shale
2172	2292	Shale	3343	3436	Conglomerate
2292	2769	Lime & shale	3436	3582	Dolomite
2769	2812	Lime	3582	3650	Lime
2812	2877	Shale & lime	3650	3672	Shale
2877	3017	Lime	3672	3785	Lime
3017	3074	Shale & lime	3785	3820	Sand
				3819'	Total Depth from cement floor level.

Elevation from derrick floor level 1813'.

Run 244'3" of 9-5/8" OD 43# 5s<sub>1</sub>-thd Class R, Range 3, Extreme Line Surface casing; set at 248'; cemented with 175 sacks of cement.

Top of Arbuckle Lime 3433'.

3/1/41 - Cored from 3439' to 3444' - 3' recovery of lime - no show of oil. This well was found to be dry in the Arbuckle Lime formation and was completed as a salt water input well at a total depth of 3819'.

Run 3575'8" of 6"OD 15# 8-thd E.W. casing; run 6"OD 8-thd DP thread form "Bakblu" male & female float collar and 6"OD 8-thd DP thread form "Bakblu" guide shoe; set at 3554'; cemented with 500 sacks of cement.

3/10/41 - Acidized with 4000 gals. of Halliburton acid through the casing - after acidizing the well took water at the rate of 400 bbls. per hour on 15 point vacuum.

Total Depth 3819'.

Note: All of above footages except elevation are calculated from the cement floor level.

FLD-JL 5/12/41 LPG (3) File (1)

I, the undersigned, being first duly sworn upon oath, state that this well record is true, correct and complete according to the records of this office and to the best of my knowledge and belief.

*F. P. [Signature]*  
 Name and title of representative of company

Subscribed and sworn to before me this the 12th day of May, 1941.

My Commission Expires October 21, 1944

*Louis M. [Signature]*  
 Notary Public  
 RECEIVED  
 STATE CORPORATION COMMISSION

MAY 22 1979

CONSERVATION DIVISION  
 Wichita, Kansas