

STATE OF KANSAS
STATE CORPORATION COMMISSION

15.009 .15592.0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Locate well correctly on above
Section Plat

Barton County. Sec. 24 Twp. 20 Rge. 12 E/W
Location as "NE/CNW1SW1" or footage from lines
1320' E 1320' S of NW1
Lease Owner Icer Addis
Lease Name Pete Scheufler Well No. 2
Office Address 5307 E. Central, Wichita, Kansas 67208
Character of Well (Completed as Oil, Gas or Dry Hole)
oil
Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced Aug. 22 1979
Plugging completed Aug. 31 1979
Reason for abandonment of well or producing formation
depleted
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes
Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation Depth to top Bottom Total Depth of Well 3349'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
			258'	10 3/4"	258'	none
			3323'	6"	3323'	545.21

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded back to 3270' and dumped 6 sacks of cement.

Allied Cementing, Inc. plugged well pumping in 4 sacks of bulls, 10 sacks of gel and 175 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP - 7 1979 9-7-1979


CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this card)
Name of Plugging Contractor GLENNS CASING PULLING INC.
Box 413, Ellinwood, Kansas 67526

STATE OF KANSAS COUNTY OF BARTON, ss.
Evelyn Roth (employee of owner) or (owner-or-operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of September, 1979



Jenny Kasselmann
Notary Public.

My commission expires

P. Scheufler #2

Spudded: January 6, 1941
 Drlg. Completed: January 27, 1941
 Potential Taken: January 30, 1941

Loc: 1320' E and 1320 S of NW Corner
 of Sec. 24, Twp. 20S, Rge. 12W
 Barton County, Kansas

From	To	Formation	From	To	Formation
0	186	Surface sand	2607	2705	Lime & shale
186	200	Shale	2705	2776	Lime
200	271	Red rock & shale	2776	2837	Lime & shale
271	1308	Shale & red rock	2837	2882	Lime
1308	1418	Shale	2882	2900	Soft Lime
1418	1503	Shale & lime	2900	2961	Lime
1503	1570	Lime	2961	3313	Shale & lime
1570	1911	Shale & lime	3313	3324	Shale
1911	1970	Shale	3324	3327	Dolomite
1970	2226	Lime & shale	3327	3350	Lime
2226	2607	Shale		3349'	Total depth from cement floor level.

Elevation from derrick floor level 1810'

Run 257'0" of 10-3/4" OD 40# 8-thd lapweld surface casing; set at 258';
 cemented with 250 sacks of cement.

Top of Arbuckle Lime from cement floor level 3321'.

Run 3342'7" of 6" OD 15# 8R-thd J-55 E.W. casing; set at 3323'; cemented
 with 250 sacks of cement.

Total fillup with oil 3000' - Swabbed 78 barrels of oil in 3 hours.

1/29/41 - Acidized with 2000 gallons of Morgan Company acid - Time 1 hour
 and 22 minutes - Maximum pressure on casing 750# - On tubing 400# - Pressure
 equalized to 400# - Used 17 barrels of load oil.

1/30/41 - Established an Echometer potential of 1484 barrels of oil; no water.

Total depth from cement floor level 3349'.

FLD-JL 2/21/41
 LPC (3)
 File (1)

RECEIVED
 OIL & GAS COMMISSION

MAY 22 1979

CLASSIFICATION DIVISION
 Wichita, Kansas

I, the undersigned, being first duly sworn upon oath, state that this
 well record is true, correct and complete according to the records of this
 office and to the best of my knowledge and belief.

7. P. D.
 Name and title of representative of company

Subscribed and sworn to before me this the 21st day of February, 1941.
 My Commission expires October 24, 1944 Louis M. Kline
 Notary Public