

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-23,888-0000

LEASE NAME Spece

WELL NUMBER 2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 24 TWP. 20 SRGE. 12 (E) or (W)

COUNTY Barton

Date Well Completed

Plugging Commenced 5-3-96

Plugging Completed 5-7-96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Globe Operating, Inc.

ADDRESS P.O. Box 12 Great Bend, Ks. 67530

PHONE#(316) 792-7607 OPERATORS LICENSE NO. 6170

Character of Well Oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3425'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	299'	none
				5 1/2"	3425'	2223'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s
Plugged off bottom with sand to 3093' and 5 sacks cement. Shot casing at 2517', and @ 2223'
Pulled casing up to 1400' pumped 100 sacks cement with 300# hulls, Pulled up to 600' pumped
40 sacks cement with 200# hulls, pulled to 284' circulated to surface with 60 sacks cement
Pulled casing, and topped off with 20 sacks cement. 60/40 10% gel) Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Globe Operating, Inc. --Great Bend, Ks.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact
statements and matters herein contained and the log of the above-described well as filed to
the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 8th day of May, 1996

James Derberg
Notary Public

My Commission Expires:



RECEIVED
KANSAS CORPORATION
MAY 10 1996