


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Barton County, Sec. 23 Twp. 20S Rge. 12W (E) (W)
Location as "NE/CNW/SW" or footage from lines C W/2 NW SE
Lease Owner Alpine Oil & Royalty Co., Inc.
Lease Name Biege Well No. 1
Office Address 800 Bitting Building, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed October 31, 1968 19
Application for plugging filed October 31, 1968 (by phone) 19
Application for plugging approved October 31, 1968 (by phone) 19
Plugging commenced October 31, 1968 19
Plugging completed October 31, 1968 19
Reason for abandonment of well or producing formation Nonproductive of oil
in commercial quantities
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	244'	Cemented
<div>RECEIVED STATE CORPORATION COMMISSION NOV 8 1968 CONSERVATION DIVISION Wichita, Kansas 11-8-1968</div>						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud from total depth to 400 feet. Plug and 40
sacks cement at 400 feet. Heavy mud to 220 feet. Second
plug set at 220 feet with 20 sacks cement. Third plug set at
40 feet with 1/2 sacks hulls and 10 sacks cement. Two
sacks cement for rat hole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.


Dwight J. Wilson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Dwight J. Wilson800 Bitting Bldg., Wichita, Kansas 67202
(Address)SUBSCRIBED AND SWORN TO before me this 31st day of October, 19 68Evelyn Wanko
Evelyn Wanko

Notary Public.

December 10, 1968



GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

BIEGE #1
W/2 NW SE Section 23-20S-12W
Barton County, Kansas

Commenced: October 23, 1968
Completed: October 31, 1968

OPERATOR - Alpine Oil & Royalty Co., Inc.

DEPTH	FORMATION	REMARKS
From To		
0 241	Sand and shale	Ran 6 joints of 8-5/8" casing, set @ 241' w/240 sacks cement.
241 584	Red bed	
584 605	Anhydrite	
605 1475	Shale and shells	
1475 2760	Shale and lime	
2760 2962	Lime	
2962 3120	Lime and shale	
3120 3370	Lime	
3370 3376	Lime and shale	
3376 3390	Lime	
3390 3420	Lime and sand	
3420 3476	Lime	
3476 TD		Dry and abandoned.

RECEIVED
STATE CORPORATION COMMISSION
NOV 8 1968
CONSERVATION DIVISION
Wichita, Kansas

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the W/2 NW SE Section 23-20S-12W, Barton County, Kansas, to the best of my knowledge and belief.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 5th day of November, 1968, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972

Barbara J. Layton
Barbara J. Layton, Notary Public

