

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 COLORADO DERRY BUILDING  
 WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-009-20615-0000

TYPE OR PRINT  
 PLEASE FILL OUT COMPLETELY  
 AND MAKE REQUIRED AFFIDAVIT.

LEASE NAME Churchill #2

WELL NUMBER \_\_\_\_\_

SPOT LOCATION NE NE SW

SEC. 22 TWP. 20s RGE. 12w (E) OR (W)

COUNTY Barton

DATE WELL COMPLETED \_\_\_\_\_

PLUGGING COMMENCED 10/6/83

PLUGGING COMPLETED 10/11/83

LEASE OPERATOR Clarence Marker

ADDRESS Box 161, 415 W. 15th, Ellinwood, Ks. 67526

PHONE # ( ) \_\_\_\_\_ OPERATORS LICENSE NO. \_\_\_\_\_

CHARACTER OF WELL  
 (OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Hays

IS ACC-1 FILED? \_\_\_\_\_ IF NOT, IS WELL LOG ATTACHED? \_\_\_\_\_

PRODUCING FORMATION \_\_\_\_\_ DEPTH TO TOP \_\_\_\_\_ BOTTOM T.D. 3445'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS | CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	244'	none
				5 1/2"	3444'	2743'

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

Bottom hole plug back with 5 cement, sand to 3350' & 5 sacks cement. Shot pipe at 2745'. Pulled total of 86 joints. Plugged well with 4 hulls, 25 cement, 10 gel, 1/2 sk hulls, 40 cement, 5 gel, 1/2 sk hulls, plug & 100 cement. Plugging complete.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE No. 6050  
 ADDRESS Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) R. Darrell Kelso

(ADDRESS) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO BEFORE ME THIS 21st DAY OF October, 1983



Irene Hoover  
 NOTARY PUBLIC

MY COMMISSION EXPIRES: \_\_\_\_\_

RECEIVED  
 STATE CORPORATION COMMISSION FORM CP-4  
 OCT 24 1983 REVISED 06-83  
 CONSERVATION DIVISION  
 Wichita, Kansas  
10-24-1983