

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

15.009.22206.0000
 Form CP-4
 Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Barton SEC. 22 TWP. 20 RGE. 12 NE/W
 Location as in quarters or footage from lines:
NE/NW/SE

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

Lease Owner Condor Energy
 Lease Name A.J. & Ruby Wilson Well No. #1
 Office Address P. O. Box 108 - Great Bend, Ks. 67530
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced January 24, 1983
 Plugging completed January 31, 1983
 Reason for abandonment of well or producing formation Depleted

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel
 Producing formation _____ Depth to top _____ bottom _____ T.D. 3450'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

| Formation | Content | From | To | Size | Put in | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 261' | NONE |
| | | | | 4 1/2" | 3449' | 2651.11' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Dumped four (4) sacks cement, 50' sand and four (4) sacks cement.
 Shot pipe @ 3000', 2800' and 2600'.
 Pulled eighty-one (81) joints 4 1/2" casing.
 Squeezed well with four (4) sacks hulls, seventeen (17) sacks gel,
 one hundred sixty-five (165) sacks 50/50 pozmix cement with
 4% added gel and 3% calcium chloride.

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
 JAMES W. ROCKHOLD / Box 698 - Great Bend, Ks.
 (Address) 67530

SUBSCRIBED AND SWORN TO before me this 31st day of February, 1983

My Commission expires: 

Margaret Prosser
 Notary Public.
 STATE CORPORATION COMMISSION

FEB 4 1983
 2-4-1983
 WICHITA, KANSAS