


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 22 Twp. 20S Rge. 12W (E) (W)
Location as "NE/CNW'SW" or footage from lines NW NW NW
Lease Owner ALPINE OIL & ROYALTY CO., INC.
Lease Name STECKEL NO. 10-A Well No. _____
Office Address 800 Bitting Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed Nov. 13, 1963 19____
Application for plugging filed November 13, 1963 19____
Application for plugging approved November 13, 1963 19____
Plugging commenced November 13, 1963 19____
Plugging completed November 13, 1963 19____
Reason for abandonment of well or producing formation non-productive in commercial quantities
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truand
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3460 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	242'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud from 3460 to 240 feet - 1/4th sacks hulls and ~~sk~~ plug at 240 feet; 25 sacks cement through drill pipe - mud to 40 feet - 1/4 th sack hulls and plug and 10 sacks cement on top - 2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

FEB 11 1964

2-11-1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Quaker Drilling Co., Inc.
Address 800 Bitting Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
THOMAS M. Mc Caul

(employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. Mc Caul
800 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of NOV, 19 63

My commission expires August 10, 1965

Virginia Wendell
Notary Public.



15.009.05221.0000

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: November 4, 1963

Contractor: Quaker Drilling Co., Inc.

Completed: November 13, 1963

No. 10-A Steckel
NW NW NW Sec. 22-20S-12W
Barton County, Kansas

Elevation: 1839 KB

Production: D & A

Casing Record

8 5/8 inch casing set at 242 feet with 225 sacks cement

(Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Surface Soil & Gravel	180	Heebner	3022 -1183
Shale and Shells	242	Brown Lime	3143 -1304
Red Bed	625	Lansing	3157 -1318
Anhydrite	653	Base of Kansas City	3380 -1541
Shale and Shells	1430	Arbuckle	3410 -1571
Lime and Shale	2845	Rotary Total Depth	3460 -1621
Lime	2910		
Lime and Shale	3460		

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the NW NW NW Section 22, Township 20 South, Range 12 West, Barton County, Kansas.

QUAKER DRILLING CO., INC.

By: 
Thomas M. McCaul

SUBSCRIBED AND SWORN TO BEFORE ME A NOTARY PUBLIC THIS 25th day of November, 1963.


Virginia Mundell, Notary Public

MY COMMISSION EXPIRES:
August 10, 1965

RECEIVED
STATE CORPORATION COMMISSION

FEB 11 1964

CONSERVATION DIVISION
Wichita, Kansas