



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM.
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUN 30 1969

CONSERVATION DIVISION
 Wichita, Kansas

6-30-1969

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Andy Leinmiller of A. L. Abercrombie, Inc., has this

date requested permission to plug the following described well:

Mr. Leinmiller guarantees payment of the plugging fee.

Operator's full Name: A. L. Abercrombie, Incorporated,

Complete Address: 801 Union Center Building, Wichita, Kansas.

Lease Name: Clark Well No. 3

Location: NW-NW-NW Sec. 8 Twp. 23 Rge. (E)(W) 17

County: Pawnee Total Depth 4310 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Leinmiller was instructed to plug the well as follows:

232'--8 5/8" Surface casing, cement circulated with 200 Sx.

4308'--5 1/2" casing cemented on bottom with 100 Sx. Well plugged back to 4270'. Top perforations from 4230' to 4240'.

Sand well back to 4200' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 20 sacks gel and follow with 130 Sx. cement.

Very truly yours,

Conservation Division Agent