

15-145-20010-0000

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 25 1967

CONSERVATION DIVISION
WICHITA, Kansas

5-25-1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Cline of Messman & Rinehart Oil Co. has this

date requested permission to plug the following described well:

Mr. Cline guarantees payment of the plugging fee.

Operator's full Name: Messman-Rinehart Oil Company

Complete Address: 1432 Wichita Plaza Wichita, Kansas

Lease Name: Frick Well No. 1

Location: C NW SW Sec. 13 Twp. 23 Rge. 17 (E)(W) X

County Pawnee Total Depth 4345 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cline was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 500' and displace

25 sc cement thru drill pipe, Heavy mud to 300' set cementing plug and

displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sc hulls and 8 sc cement to base of cellar. Plug rat hole

with 2 sc cement.

Very truly yours,

Leo F. Messer
Conservation Division Agent