



15.009.15594.0000

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 1 1965

CONSERVATION DIVISION
Wichita, Kansas

3-1-1965

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. J. M. Glickman of Glickman Oil Co. has this
date requested permission to plug the following described well:

Mr. J. M. Glickman guarantees payment of the plugging fee.

Operator's full Name: Glickman Oil Company

Complete Address: 702 S. St. Francis, Wichita, Kansas

Lease Name: P. Scheufler Well No. # 4

Location: NW SW NW Sec. 24 Twp. 20 Rge. 12 (E) (W) W

County Barton Total Depth 3372 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Bob Barnes was instructed to plug the well as follows:

9 5/8" 239' Cwc. plug 3210'. Perf. 2973'.

Set bottom plug @ 2960' & dumped 5 sax cement with dump
bailer. Pulled pipe. Mudded hole to 235'; set rock bridge,
& 4 sax cement with dump bailer. Let set over-nite. Bailed
hole dry; displaced 25 sax cement. Mud to 35'; set rock
bridge & displaced 10 sax cement, cementing to base of
cellar.

Very truly yours,
Joseph T. Duman
Conservation Division Agent