

State of Kansas



15.009.15599.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 13 1966

CONSERVATION DIVISION
Wichita, Kansas

12-13-1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. A. T. Slagle of Phillips Petroleum, Co. has this
date requested permission to plug the following described well:

Mr. Phillips Pet. Co. guarantees payment of the plugging fee.

Operator's full Name: Phillips Petroleum Company

Complete Address: Box 287, Great Bend, Kansas

Lease Name: York Scheufler Well No. # 1

Location: C SW SW SE Sec. 24 Twp. 20 Rge. 12 (E)(W) W

County Barton Total Depth 3371 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Darrel Kelso was instructed to plug the well as follows:

8 5/8" 265' Cwc.

Sanded hole back to 3100' & dumped 5 sax cement with dump bailer. Pulled
pipe. Bailed hole dry to 250', set 10' rock bridge, & displaced 25 sax
cement. Mud to 40', set rock bridge, & displaced 10 sax cement,
cementing to base of cellar.

Very truly yours,

Don L. ...
Conservation Division Agent