


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Barton County. Sec. 22 Twp. 20S Rge. 12W (E) (W)  
Location as "NE/CNW/SW" or footage from lines NW NW SE  
Lease Owner ALPINE OIL & ROYALTY CO., INC.  
Lease Name LOUISE ROLES Well No. 1  
Office Address 800 Bitting Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil well  
Date well completed August 4, 1957 19  
Application for plugging filed December 4, 1958 19  
Application for plugging approved December 4, 1958 19  
Plugging commenced December 4, 1958 19  
Plugging completed December 11, 1958 19  
Reason for abandonment of well or producing formation non-productive in commercial quantities  
If a producing well is abandoned, date of last production November 28 19 58  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Donald Truan  
Producing formation Arbuckle Depth to top 3381 Bottom \_\_\_\_\_ Total Depth of Well 3440 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	250	Cemented
				5 1/2"	3440	2534.24

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded to 3420 feet - dumped 5 sacks cement - mudded hole to 250'  
Cement - mudded to 40' - set 10' rock bridge - dumped 10 sacks cement  
to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & D Casing Pulling Company  
Address Box 569 - Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Thomas M. McCaul (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. McCaul

X 800 Bitting Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of December 1958

My commission expires August 10, 1961

Virginia M. Muddell  
Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

PLUGGING  
FILE SEC. 22 T. 20 R. 12W  
BOOK PAGE 1 LINE 40

JAN 3 1959  
1-3-1959  
CONSERVATION DIVISION  
Wichita, Kansas

## WELL LOG

ALPINE OIL &amp; ROYALTY CO., INC.

Commenced: July 7, 1957

Contractor: Quaker Drilling Co., Inc.

Completed: July 18, 1957

Louise Rolfs No. 1  
NW NW SE Sec. 22-20S-12W  
Barton County, Kansas

Elevation: 1830 KB

## Casing Record:

Set 8 5/8 inch casing at 250 feet with 225 sacks pozmix.  
Set 5 1/2 inch casing at 3440 feet with 150 sacks pozmix.

(Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Surface Soil & Sand	173	Anhydrite	605
Shale	250	Heebner	3008 -1178
Red Bed	540	Brown Lime	3133 -1303
Sand	605	Lansing	3147 -1317
Anhydrite	635	Base of Kansas City	3372 -1542
Shale	700	Arbuckle	3381 -1551
Shale and Shells	1549	Rotary Total Depth	3440 -1610
Hard Hard Lime	1660		
Sandy Lime and Shale	1963		
Shale and Lime	2673		
Lime and Shale & Sand	2810		
Lime and Shale	3141		
Lime	3200		
Lime and Shale	3285		
Lime	3311		
Lime and Shale	3381		
Dolomite and Shale	3440		

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the NW NW SE of Section 22, Township 20 South, Range 12 West, Barton County, Kansas.

QUAKER DRILLING CO., INC.

*Thomas M. McCatal*  
By: Thomas M. McCatal, President

SUBSCRIBED AND SWORN TO before me a Notary Public in and for Sedgwick County, Kansas this 20th day of July, 1957.

MY COMMISSION EXPIRES:  
August 10, 1957.

*Virginia Mandell*  
Virginia Mandell, Notary Public

RECEIVED  
STATE CORPORATION COMMISSION

JAN 3 1959

CONSERVATION DIVISION  
KANSAS

PLUGGING	
FILE	SEC. 22 T. 20 R. 12W
BOOK	PAGE 1 LINE 40